

**UNIT PRICE LIST FOR
BROOKS CITY-BASE BLDG. 775 PARKING LOT LIGHTING STRIPING**

3/25/2013

DESCRIPTION	UNIT	QTY	BIDDER	
			UNIT	AMOUNT
Mobilization	LS	1		
Insurance and Bond	LS	1		
Demolition & Site Preparation	LS	1		
Parking Lot Striping	LS	1		
Light Fixture A-ACUITY BRANDS LIGHTING #MR1 150MHC SR2 TB RPA DNA LP1	EA	17		
Light Fixture B -ACUITY BRANDS LIGHTING #MR2 250MHC SR3 TB RPA DNA LP1	EA	14		
Light Fixture C - ACUITY BRANDS LIGHTING #MR2 250MHC SR3 TB RPA DNA LP1	EA	12		
Light Fixture D -ACUITY BRANDS LIGHTING #MR2 250MHC SR3 TB RPA DNA LP1	EA	14		
Pole A - RTA-16-305F-N-PNA-D1- ROUND TAPER ALUM.	EA	15		
Pole B - RTA-18-305F-N-PNA-D2-ROUND TAPER ALUM.	EA	7		
Pole C - RTA-20-305F-N-PNA-D2-ROUND TAPER ALUM.	EA	6		
Pole D - RTA-18-305F-N-PNA-D2-ROUND TAPER ALUM.	EA	12		
Pole A-D - RTA-18-305F-N-PNA-D2-ROUND TAPER ALUM. (Modified to allow for one "D" and one "A" Fixture)	EA	2		
2" Conduit Elbow 36" Schedule 40	EA	4		
2" Conduit Elbow 30" Schedule 40	EA	21		
1" Conduit Elbow 30" Schedule 40	EA	106		
1" Conduit Elbow 36" Schedule 40	EA	2		
2" Schedule 40 PVC Conduit	LF	1003		
1" Schedule 40 PVC Conduit	LF	3490		
#2 600v Insulated 600v Cable (Color Coded THHN)	LF	2282		
#8 600v Insulated 600v Cable (Color Coded THHN)	LF	13774		
#12 600v Insulated 600v Cable (Color Coded THHN)	LF	1597		
1/0 CU 600v Insulated 600v Cable	LF	*		
Secondary Enclosure (Nordic PHH-161918-MG or Equivalent)	EA	15		

**UNIT PRICE LIST FOR
BROOKS CITY-BASE BLDG. 775 PARKING LOT LIGHTING STRIPING**

3/25/2013

6-Outlet Connector (Insulated) (HOMAC RAB65 or Equivalent)	EA	26		
5-Outlet Set Screw Bar (HOMAC ABC5350 or Equivalent)	EA	13		
3-Outlet Connector (Insulated) (HOMAC RAB-3 or Equivalent)	EA	12		
7-Outlet Set Screw Bar (HOMAC ABC7350 or Equivalent)	EA	2		
#6 SD CU Wire	LF	*		
5/8"X8" Copperweld Ground Rod	EA	17		
Bronze Ground Rod Clamp	EA	17		
Fuse Kit With Fuse-10 AMP (Elastimold 65U or Equivalent)	EA	84		
Control Contractor (Ripley CC1002NOEISWHPMI WITH PHOTO CONTROL RT 8394)	EA	2		
2"X8' Galvanized Rigid Pipe (Supports per CPS Energy)	EA	4		
Galvanized Unistrut (per ft.)	LF	36		
2" Galvanized Rigid Conduit	LF	*		
2" Galvanized Caps	EA	4		
Weatherproof 125 AMP Breaker Panel 600 V	EA	2		
50 AMP Breakers	EA	6		
200 AMP Meter Can	EA	2		
1/2" Galvanized Rigid Conduit	LF	*		
2" Galvanized Pipe Straps	EA	*		
1/2" Galvanized Pipe Straps	EA	*		
3" SCH 40 PVC (Grey) Conduit for CPS Service	LF	30		
3" RMC Elbows at CPS Riser Pole for CPS Service	EA	2		
8 Sackrete	EA	8		
* Misc. Materials (Required Per Details)				
BASE BID SUBTOTAL				
ADD ALTERNATE NO. 1				
Seal Coat	SY	19,300		
ALTERNATE NO. 1 SUBTOTAL				
BASE BID				
BASE BID + ADD ALTERNATE NO. 1				