



ADDENDUM NUMBER 2
Sidney Brooks Memorial & Gravesite Renovation
Clarifications
Bid #12012014-001

To: All Attending Bidders

From: Lucynda Massey, Accounting, Procurement, & Contracts Coordinator

Date: December 19, 2014

.....
SPECIFICATIONS

SECTIONS 017329 CUTTING AND PATCHING, 024119 SELECTIVE DEMOLITION,
AND 311000 SITE CLEARING – Clarification:

Clean soils to be excavated and removed from the project site may be stockpiled by the Contractor at the southwest area of Brooks City Base property on Stealth Road, approximately 3/4 of a mile from the Sidney Brooks Gravesite project. The soils shall contain no debris and shall be clean of all concrete, asphalt, rocks over 2” in size, tree roots or stumps. All other demolished material, not including clean soils or items scheduled to be salvaged for reinstallation, shall be hauled off site and legally disposed at the Contractor’s expense.



DRAWINGS

RE: ELECTRICAL DRAWINGS SHEET ESD1.1:

Revise Keyed Note #4 to read, "Remove ground mounted flood lights (7 fixtures) imbedded in surrounding concrete pad and return to BDA. Ground mounted flood lights (4 fixtures) imbedded in concrete footing supporting statue base shall remain. Associated circuitry shall be reconfigured so that the remaining lighting fixtures remain in operation."



END OF ADDENDUM NUMBER 2