

BROOKS CITY BASE #2 PAPE BLDG 775 TX A&M STAKING SHEETS
PHASE 1A-NEW LIGHT FIXTURES PART 2

Const Pts		Qty	INSTALL ITEMS	NOTES
At	To			
49	50	120'	TR-1	
		120'	1" SCH 40 Conduit	
		135'	SEC-1	3-#8 600v Insulated CU Cable (120' plus make-up)
		40'	Lamp Wire	3-#12 600v Insulated CU Cable
		2	1" Conduit Elbow-30"	
		1	Street Light-D	
		2	Fuse Kit	
50	51	120'	TR-1	
		120'	1" SCH 40 Conduit	
		135'	SEC-1	3-#8 600v Insulated CU Cable (120' plus make-up)
		40'	Lamp Wire	3-#12 600v Insulated CU Cable
		2	1" Conduit Elbow-30"	
		1	Street Light-D	
		2	Fuse Kit	
51		37'	Lamp Wire	3-#12 600v Insulated CU Cable
		1	1" Conduit Elbow-30"	
		1	Street Light-D	
		2	Fuse Kit	
44	52	72'	TR-1	
		72'	1" SCH 40 Conduit	
		82'	SEC-1	3-#8 600v Insulated CU Cable (72' plus make-up)
		2	1" Conduit Elbow-30"	

BROOKS CITY BASE #2 PAPE BLDG 775 TX A&M STAKING SHEETS
PHASE 1A-NEW LIGHT FIXTURES PART 2

Const Pts		Qty	INSTALL ITEMS	NOTES
At	To			
55		45'	Lamp Wire	6-#12 600v Insulated CU Cable
		1	1" Conduit Elbow-30"	
		1	Street Light-C	
		2	Fuse Kit	
32	33	60'	TR-1	
		60'	1" SCH 40 Conduit	
		70'	SEC-1	3-#8 600v Insulated CU Cable (60' plus make-up)
		1	1" Conduit Elbow-30"	
33	34	60'	TR-1	
		60'	1" SCH 40 Conduit	
		75'	SEC-1	3-#8 600v Insulated CU Cable (60' plus make-up)
		35'	Lamp Wire	3-#12 600v Insulated CU Cable
		2	1" Conduit Elbow-30"	
		1	Street Light-A	
		2	Fuse Kit	
34	35	87'	TR-1	
		35'	BORE	
		122'	1" SCH 40 Conduit	
		137'	SEC-1	3-#8 600v Insulated CU Cable (122' plus make-up)
		35'	Lamp Wire	3-#12 600v Insulated CU Cable
		2	1" Conduit Elbow-30"	
		1	Street Light-A	
		2	Fuse Kit	

